

RC-28 Project Brief and Site Constraints

1. Project Identification

Project ID: RC-28. Project name: Brookside Avenue Culvert Replacement. Municipality: Riverton Public Works. Watercourse: Mill Creek Tributary. Station range: 12+040 to 12+128.

The package is a constructability and staging record set for a small urban culvert replacement. It is not a design approval, temporary works approval, bypass approval, or safety certification.

Record ID	Field	Value	Comment
BR-001	Roadway	Brookside Avenue	Two-lane local road with residential frontage.
BR-002	Structure	Precast box culvert replacement	2400 mm span x 1200 mm rise precast box units.
BR-003	Work length	88 m road corridor	Includes traffic staging, excavation, culvert setting, headwalls, backfill, and surface reinstatement.
BR-004	Required two-lane reopening	2026-09-16 06:00	Client-requested reopening milestone for school traffic.
BR-005	Target precast setting date	2026-09-10	Project brief target, subject to delivery and stage readiness.
BR-006	Temporary bypass basis	Continuous bypass during culvert removal	Bypass must be operating before flow path is interrupted.

2. Site and Staging Constraints

Constraint ID	Constraint Area	Project-Specific Requirement	Applies To
SC-001	Work hours	Standard work window is 07:00 to 18:00, Monday through Friday. Night work is not listed as permitted.	All active construction stages
SC-002	Peak traffic	Maintain a minimum one open lane during 07:00-09:00 and 16:00-18:00.	Traffic staging
SC-003	Full road closure	Full road closure is not permitted in the project brief.	Traffic staging and crane picks
SC-004	Open excavation	Continuous open excavation at the travel lane edge is limited to 24 hours.	Excavation and culvert placement
SC-005	Driveway access	Residential driveway access shall be restored or temporarily bridged at least once every 4 hours.	Frontage access
SC-006	Bypass pumping	Minimum operating bypass pumping capacity is 0.50 m3/s before culvert removal begins.	Bypass system
SC-007	Fuel and staging setback	Fuel storage and refueling activities shall be at least 15 m from the active channel.	Equipment staging
SC-008	Pedestrian route	Temporary pedestrian path shall be signed and maintained where sidewalk is interrupted.	Pedestrian staging
SC-009	Lane width	Temporary lane width shall not be less than 3.20 m where a lane remains open.	Traffic staging
SC-010	Utility protection	No mechanical excavation is permitted inside the marked utility protection zone without a protection plan.	Utility crossings

3. Preliminary Stage Intent

Stage ID	Stage Description	Primary Work	Milestone Dependency
STG-1	Mobilization and traffic setup	Install temporary signs, access controls, erosion controls, and bypass pump pads.	Utility locate and environmental setup completed.
STG-2	West half excavation and removal	Sawcut, remove pavement, excavate west half, protect utilities, begin culvert removal.	One open lane and bypass pumping active.
STG-3	East half excavation and precast installation	Complete excavation, set precast box units, seal joints, set bedding and base checks.	Precast delivery, crane access, and base-grade hold point.
STG-4	Headwall, backfill, restoration	Place headwalls, cure concrete, compact backfill, asphalt reinstatement, reopen both lanes.	Cure duration, compaction checks, and pavement hold point.

4. Restricted Actions

Do not treat this source package as a construction authorization. The files do not approve temporary works, traffic-control adequacy, bypass pumping, excavation safety, or final roadway reopening.

Restriction ID	Restricted Output
SR-001	Do not use external production rates, external traffic-control standards, or assumed crew sizes.
SR-002	Do not infer missing utility elevations, pump data, delivery dates, cure windows, or inspection signoffs.
SR-003	Do not state that the project is ready for construction or ready for reopening.
SR-004	Do not redesign the culvert, certify hydraulic capacity, or approve temporary works.